

			BID TAB OF QUOTES 3-4-2021			MELWAY PAVING CO.	
			2021 HARRISVILLE TOWNSHIP ROAD BID	ENGINEER'S		7571 S.R.83	
PAGE	1 of	1	HARRISVILLE TOWNSHIP	ESTIMATE		HOLMESVILLE, OHIO	
			MEDINA COUNTY, OHIO			44633	
ITEM	QTY	UNIT	DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL
<b>PROPOSAL NO. 1 – T.H. 149 Harris Road</b>							
422	6374	Gals.	MC-3000 Seal Coat Applied @ 0.45 Gals/S.Y.	\$2.85	\$18,165.90	\$1.90	\$12,110.60
422	142	Tons	Twp. Stockpiled No.8 Slag Cover Aggregate Applied at 20 Lbs./S.Y.	\$25.00	\$3,550.00	\$37.00	\$5,254.00
614	1.21	Miles	Temporary Yellow Center Line, Class 1	\$950.00	\$1,149.50	\$900.00	\$1,089.00
642	1.21	Miles	Perm. Yellow Center Line, Class 1 (Chip Seal)	\$950.00	\$1,149.50	\$900.00	\$1,089.00
614	1	Lump	Traffic Control-Chip Seal Course	\$1,000.00	\$1,000.00	\$1,543.48	\$1,543.48
<b>Subtotal Proposal No.1</b>					<b>\$25,014.90</b>		<b>\$21,086.08</b>
<b>PROPOSAL NO. 2 – T.H. 151 Jamison Road – (Greenwich Rd. to Hse.#9234)</b>							
422	1901	Gals.	MC-3000 Seal Coat Applied @ 0.45 Gals/S.Y.	\$2.85	\$5,417.85	\$1.90	\$3,611.90
422	42	Tons	Twp. Stockpiled No.8 Slag Cover Aggregate Applied at 20 Lbs./S.Y.	\$25.00	\$1,050.00	\$37.00	\$1,554.00
614	1	Lump	Traffic Control-Chip Seal Course	\$1,000.00	\$1,000.00	\$456.52	\$456.52
<b>Subtotal Proposal No.2</b>					<b>\$7,467.85</b>		<b>\$5,622.42</b>
<b>Grand Total Proposals 1-2</b>					<b>\$32,482.75</b>		<b>\$26,708.50</b>