

			BID TAB OF QUOTES 3-04-2021 2021 YORK TOWNSHIP ROAD BID		ENGINEER'S ESTIMATE		MELWAY PAVING CO. 7571 STATE ROUTE 83 HOLMESVILLE, OHIO 44633		CROSSROADS ASPHALT 13421 HAWKE ROAD COLUMBIA STATION, OHIO 44028		PERK COMPANY, INC. 8100 GRAND AVE. SUITE 100 CLEVELAND, OHIO 44104	
PAGE	1 of	1	YORK TOWNSHIP MEDINA COUNTY, OHIO									
ITEM	QTY	UNIT	DESCRIPTION		UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
Proposal No. 1 – T.H. 165 Stiegler Road – (York Twp. Line to Wolff Rd.)												
253	25	C.Y.	6" Depth Pavement Repairs		\$250.00	\$6,250.00	\$210.00	\$5,250.00	\$205.00	\$5,125.00	\$250.00	\$6,250.00
422	2378	Gals.	CSR-2P Seal Coat Applied at 0.45 Gal./S.Y.		\$2.85	\$6,777.30	\$2.00	\$4,756.00	\$2.50	\$5,945.00	\$2.00	\$4,756.00
422	53	TON	No. 8 ACBF Slag Applied at 20 Lbs./S.Y.		\$70.00	\$3,710.00	\$75.00	\$3,975.00	\$65.00	\$3,445.00	\$120.00	\$6,360.00
642	0.44	Miles	Temporary Yellow Center Line, Class 1		\$950.00	\$418.00	\$1,100.00	\$484.00	\$1,100.00	\$484.00	\$1,200.00	\$528.00
642	0.44	Miles	Yellow Center Line, Class 1		\$950.00	\$418.00	\$1,100.00	\$484.00	\$1,100.00	\$484.00	\$1,200.00	\$528.00
642	0.88	Miles	White Painted Edge Line, Class 1		\$900.00	\$792.00	\$550.00	\$484.00	\$550.00	\$484.00	\$1,200.00	\$1,056.00
642	20	L.F.	White Painted Stop Bar, Class 1		\$5.00	\$100.00	\$3.00	\$60.00	\$3.00	\$60.00	\$15.00	\$300.00
614	1	LUMP	Traffic Control		\$800.00	\$800.00	\$2,541.93	\$2,541.93	\$2,350.00	\$2,350.00	\$1,100.00	\$1,100.00
Subtotal Proposal No.1						\$19,265.30		\$18,034.93		\$18,377.00		\$20,878.00
Proposal No. 2 – T.H. 166 Gayer Road – (York Twp. Line to Hamilton Rd.)												
253	25	C.Y.	6" Depth Pavement Repairs		\$250.00	\$6,250.00	\$210.00	\$5,250.00	\$205.00	\$5,125.00	\$250.00	\$6,250.00
422	887	Gals.	CSR-2P Seal Coat Applied at 0.45 Gal./S.Y.		\$2.85	\$2,527.95	\$2.00	\$1,774.00	\$2.50	\$2,217.50	\$2.00	\$1,774.00
422	20	TON	No. 8 ACBF Slag Applied at 20 Lbs./S.Y.		\$70.00	\$1,400.00	\$75.00	\$1,500.00	\$75.00	\$1,500.00	\$120.00	\$2,400.00
642	0.17	Miles	Temporary Yellow Center Line, Class 1		\$950.00	\$161.50	\$2,350.00	\$399.50	\$2,350.00	\$399.50	\$1,250.00	\$212.50
642	0.17	Miles	Yellow Center Line, Class 1		\$950.00	\$161.50	\$2,350.00	\$399.50	\$2,350.00	\$399.50	\$1,250.00	\$212.50
642	0.34	Miles	White Painted Edge Line, Class 1		\$900.00	\$306.00	\$700.00	\$238.00	\$700.00	\$238.00	\$1,250.00	\$425.00
642	20	L.F.	White Painted Stop Bar, Class 1		\$5.00	\$100.00	\$3.00	\$60.00	\$3.00	\$60.00	\$15.00	\$300.00
614	1	LUMP	Traffic Control		\$800.00	\$800.00	\$836.07	\$836.07	\$1,950.00	\$1,950.00	\$1,100.00	\$1,100.00
Subtotal Proposal No.2						\$11,706.95		\$10,457.07		\$11,889.50		\$12,674.00
Grand Total Proposals No. 1-5						\$30,972.25		\$28,492.00		\$30,266.50		\$33,552.00