

				BID TAB OF QUOTES OF QUOTES 7-11-2022 LITCHFIELD TOWNSHIP ROAD BID 2022 MEDINA COUNTY, OHIO	ENGINEERS ESTIMATE		MELWAY PAVING CO., INC. 7571 SR 83 HOLMESVILLE, OHIO 44633	
REF NO.	ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL
1	253	50	C.Y.	301 Pavement Repairs – Average 4" Full Depth	\$230.00	\$11,500.00	\$300.00	\$15,000.00
2	422	8751	Gal	CRS-2P Bituminous Latex Modified Seal Coat Applied @ 0.45 Gal/SY	\$3.00	\$26,253.00	\$4.15	\$36,316.65
3	422	196	Tons	No. 8 ACBF Slag Cover Aggregate @ 20 Lbs/SY	\$90.00	\$17,640.00	\$70.00	\$13,720.00
4	614	1.63	Miles	Temporary Center Line, Class 1 (422)	\$1,500.00	\$2,445.00	\$2,000.00	\$3,260.00
5	642	1.63	Miles	Yellow Painted Center Line, Class 1	\$1,500.00	\$2,445.00	\$2,000.00	\$3,260.00
6	642	12	LF	24" Wide White Painted Stop Bar	\$6.00	\$72.00	\$15.00	\$180.00
7	642	2	Each	Railroad Symbol Marking, Type 1	\$300.00	\$600.00	\$500.00	\$1,000.00
8	624	1	Lump	Mobilization	\$2,000.00	\$2,000.00	\$2,500.00	\$2,500.00
9	614	1	Lump	Furnish & Maintain Vehicular Traffic Control	\$2,500.00	\$2,500.00	\$4,500.00	\$4,500.00
TOTAL						\$65,455.00		\$79,736.65