

				BID TAB OF QUOTES 1-26-2023		ENGINEER'S		Melway Paving Co., Inc.	
				CHIPPEWA LAKE MAIN DRIVE OVERLAY PROJECT		ESTIMATE		7571 SR 83,	
				LAFAYETTE TOWNSHIP, MEDINA COUNTY, OHIO				Holmesville, OH 44633	
Page 1 of 1									
REF. #	ITEM	QTY	UNIT	DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL	
1	CS405	243	Tons	Year Two: 57 Limestone Mix Aggregate applied at 150 lbs/SY	\$110.00	\$26,730.00	\$140.00	\$34,020.00	
2	CS405	4239	Gals	Year Two: CMS-2 Mix Oil at 17.5 gals/ton	\$5.00	\$21,195.00	\$2.75	\$11,657.25	
3	CS405	17	Tons	Year Two: No. 9 Limestone Choke at 10 Lbs/SY	\$40.00	\$680.00	\$30.00	\$510.00	
4	422	1776	Gals	Year Two: CRS-2P Bituminous Latex Modified Seal Coat Applied at 0.55 Gals/SY	\$5.00	\$8,880.00	\$2.75	\$4,884.00	
5	422	33	Tons	Year Two: No.8 ACBF Slag Cover @ 20 Lbs/SY	\$110.00	\$3,630.00	\$150.00	\$4,950.00	
6	617	44	C.Y.	Year Two: Shoulder Reconditioning Using No. 411 Limestone Aggregate Furnished, Spread & Rolled 24" Wide, 3" Depth	\$130.00	\$5,720.00	\$120.00	\$5,280.00	
7	703	10	C.Y.	(Optional) Top Dressing No.304/No.57 Limestone for Driveway Repair As Needed	\$130.00	\$1,300.00	\$115.00	\$1,150.00	
8	SPEC	10	C.Y.	(Optional) Driveway Wedging with 441 Type 1, Surface	\$400.00	\$4,000.00	\$225.00	\$2,250.00	
9	614	1	Lump	Furnish & Maintain Vehicular Traffic Control (per plan)	\$3,000.00	\$3,000.00	\$5,000.00	\$5,000.00	
Grand Total						\$75,135.00		\$69,701.25	