

				BID TAB OF QUOTES 1-10-2023 T.H. 124 YOST ROAD IMPROVEMENT OPWC PROJECT NO. C105Z/C106Z LITCHFIELD TOWNSHIP MEDINA COUNTY, OHIO		ENGINEER'S ESTIMATE		MELWAY PAVING COMPANY, INC. 7571 SR 83 Holmesville, OH 44633		CROSS ROADS ASPHALT RECYCLING INC. 13421 Hawke Road Columbia Station, OH 44028		KARVO COMPANIES INC. 4524 Hudson Drive Stow, Ohio 44224		CHAGRIN VALLEY PAVING, INC. 17290 Munn Road Chagrin Falls, OH 44023	
REF NO.	ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	
1	253	120	CY	301 Pavement Repairs – Average 5" Full Depth	\$300.00	\$36,000.00	\$225.00	\$27,000.00	\$250.00	\$30,000.00	\$290.00	\$34,800.00	\$400.00	\$48,000.00	
2	254	500	SY	Bituminous Pavement Planing – Butt Joints and Driveways (Grindings to Twp.)	\$5.00	\$2,500.00	\$7.50	\$3,750.00	\$18.00	\$9,000.00	\$20.00	\$10,000.00	\$15.00	\$7,500.00	
3	407	1560	Gals	"Trackless" SS-1 Bituminous Tack Coat @ 0.1 Gals/SY	\$2.50	\$3,900.00	\$2.75	\$4,290.00	\$5.00	\$7,800.00	\$3.00	\$4,680.00	\$2.00	\$3,120.00	
4	CS402	1680	Tons	2" County Spec. Intermediate Course @ 3875 Lbs/CY	\$100.00	\$168,000.00	\$110.00	\$184,800.00	\$110.00	\$184,800.00	\$99.75	\$167,580.00	\$110.00	\$184,800.00	
5	CS402	80	Tons	No. 9 Limestone Choke @ 10 Lbs/SY	\$30.00	\$2,400.00	\$25.00	\$2,000.00	\$60.00	\$4,800.00	\$40.00	\$3,200.00	\$150.00	\$12,000.00	
6	703	14745	Gals	CRS-2P Bituminous Latex Modified Seal Coat Applied @ 0.45 Gal/SY and 0.55 Gal/SY	\$3.00	\$44,235.00	\$3.00	\$44,235.00	\$3.20	\$47,184.00	\$4.00	\$58,980.00	\$2.00	\$29,490.00	
7	614	300	Tons	No. 8 ACBF Slag Cover Aggregate @ 20 Lbs/SY	\$100.00	\$30,000.00	\$90.00	\$27,000.00	\$85.00	\$25,500.00	\$150.00	\$45,000.00	\$100.00	\$30,000.00	
8	422	325	Tons	24" Wide Crushed Berm Material, 2" Depth	\$60.00	\$19,500.00	\$38.00	\$12,350.00	\$52.00	\$16,900.00	\$55.00	\$17,875.00	\$70.00	\$22,750.00	
9	422	3.74	Miles	Temporary Center Line, Class 1 (CS402 and 422)	\$1,500.00	\$5,610.00	\$1,250.00	\$4,675.00	\$1,250.00	\$4,675.00	\$1,250.00	\$4,675.00	\$1,250.00	\$4,675.00	
10	617	2.44	Miles	Yellow Painted Center Line, Class 1	\$1,500.00	\$3,660.00	\$1,250.00	\$3,050.00	\$1,250.00	\$3,050.00	\$1,250.00	\$3,050.00	\$1,250.00	\$3,050.00	
11	614	40	LF	24" Wide White Painted Stop Bar	\$6.00	\$240.00	\$6.00	\$240.00	\$6.00	\$240.00	\$6.00	\$240.00	\$6.00	\$240.00	
12	642	2	Each	Monument Adjusted to Grade	\$300.00	\$600.00	\$550.00	\$1,100.00	\$1,000.00	\$2,000.00	\$800.00	\$1,600.00	\$700.00	\$1,400.00	
13	642	1	Each	Furnish and Install Monument Box	\$500.00	\$500.00	\$550.00	\$550.00	\$1,250.00	\$1,250.00	\$950.00	\$950.00	\$1,000.00	\$1,000.00	
14	623	1	Lump	Furnish & Maintain Vehicular Traffic Control	\$6,500.00	\$6,500.00	\$8,000.00	\$8,000.00	\$18,500.00	\$18,500.00	\$25,500.00	\$25,500.00	\$60,000.00	\$60,000.00	
TOTAL						\$323,645.00		\$323,040.00		\$355,699.00		\$378,130.00		\$408,025.00	