

BID TAB OF QUOTES 02-14-2019				ENGINEER'S		U.S. BRIDGE	
T.H. 28 PAWNEE RD BRIDGE REPLACEMENT PROJECT				ESTIMATE		201 WHEELING AVENUE	
HARRISVILLE TOWNSHIP, MEDINA COUNTY, OHIO						CAMBRIDGE, OH 43725	
PAGE	1 of	1					
ITEM	QTY	UNIT	DESCRIPTION	UNIT COST	TOTAL	COST	TOTAL
202	1	Lump	Remove/Dispose of Existing Wearing Surface, Existing Corrugated Steel Bridge Flooring, Existing Bridge Mounted Guardrail Posts, and Existing Bridge Guardrail.	\$30,000.00	\$30,000.00	\$26,414.98	\$26,414.98
spec	1	Lump	Surface Preparation of Existing Top Flanges	\$10,000.00	\$10,000.00	\$5,138.69	\$5,138.69
511	2	EA.	Form, Reinforce, Pour Beam End Encasements Using Class QC1 Concrete (Optional)	\$5,000.00	\$10,000.00	\$6,692.31	\$13,384.62
511	150	Sq.Yds	Form, Reinforce, Pour Concrete Wearing Surface Using Class QC1 Concrete with 5 Lbs. Of Fiber Reinforcement per Yard	\$205.00	\$30,750.00	\$191.26	\$28,689.00
513	1913	Lbs	New A572- Grade 50 Structural Steel-Fabricated, Galvanized and Inst.	\$4.25	\$8,130.25	\$4.48	\$8,570.24
513	1344	Sq.Ft	A570-5 Gage-3x9 Bridge Flooring Galvanized and Installed	\$32.00	\$43,008.00	\$30.41	\$40,871.04
517	200	L.F.	Install Deep Beam Rail w/Steel Tubular Backup and Type 1 Steel Posts and Anchor Bolts	\$50.00	\$10,000.00	\$162.92	\$32,584.00
606	356	L.F.	Install MGS Galvanized Guardrail w/reflectors	\$18.00	\$6,408.00	\$20.00	\$7,120.00
606	3	EA.	Install Type E Guardrail Assembly per ODOT Specs	\$2,000.00	\$6,000.00	\$2,370.00	\$7,110.00
606	1	EA.	Install Type T Guardrail Assembly per ODOT Specs	\$1,000.00	\$1,000.00	\$805.00	\$805.00
606	4	EA.	Install Galvanized Bridge Terminal Assembly	\$2,000.00	\$8,000.00	\$1,275.00	\$5,100.00
606	4	EA.	Install MGS Guardrail Assembly	\$500.00	\$2,000.00	\$1,000.00	\$4,000.00
INDICATES CORRECTED FIGURE(S)							
Grand Total					\$165,296.25		\$179,787.57