

BID TAB OF QUOTES 07-06-2018															
T.H. 28 PAWNEE RD BRIDGE REPLACEMENT PROJECT															
PAGE	1 of	1	HARRISVILLE TOWNSHIP, MEDINA COUNTY, OHIO				ENGINEER'S ESTIMATE		U.S. BRIDGE 201 WHEELING AVENUE CAMBRIDGE, OH 43725		LOCKHART CONCRETE CO. 800 W. WATERLOO RD. AKRON OH 44314		SCHIRMER CONSTRUCTION LLC 31350 INDUSTRIAL PARKWAY NORTH OLMSTEAD OH 44070		AVERAGE UNIT COST
ITEM	QTY	UNIT	DESCRIPTION	UNIT COST	TOTAL	COST	TOTAL	COST	TOTAL	COST	TOTAL	COST	TOTAL	UNIT COST	
202	1	Lump	Remove/Dispose of Existing Wearing Surface, Existing Corrugated Steel Bridge Flooring, Existing Bridge Mounted Guardrail Posts, and Existing Bridge Guardrail.	\$20,000.00	\$20,000.00	\$28,436.44	\$28,436.44	\$58,425.00	\$58,425.00	\$32,000.00	\$32,000.00			\$39,620.48	
spec	1	Lump	Surface Preparation of Existing Top Flanges	\$15,000.00	\$15,000.00	\$5,603.34	\$5,603.34	\$16,000.00	\$16,000.00	\$3,500.00	\$3,500.00			\$8,367.78	
511	2	EA.	Form, Reinforce, Pour Beam End Encasements Using Class QC1 Concrete (Optional)	\$5,000.00	\$10,000.00	\$7,772.95	\$15,545.90	\$2,000.00	\$4,000.00	\$4,500.00	\$9,000.00			\$4,757.65	
511	150	Sq.Yds	Form, Reinforce, Pour Concrete Wearing Surface Using Class QC1 Concrete with 5 Lbs. Of Fiber Reinforcement per Yard	\$177.00	\$26,550.00	\$203.88	\$30,582.00	\$95.00	\$14,250.00	\$262.00	\$39,300.00			\$186.96	
513	1913	Lbs	New A572- Grade 50 Structural Steel-Fabricated, Galvanized and Inst.	\$4.25	\$8,130.25	\$2.37	\$4,533.81	\$5.00	\$9,565.00	\$12.00	\$22,956.00			\$6.46	
513	1344	Sq.Ft	A570-5 Gage-3x9 Bridge Flooring Galvanized and Installed	\$16.00	\$21,504.00	\$32.82	\$44,110.08	\$40.00	\$53,760.00	\$37.00	\$49,728.00			\$36.61	
517	200	L.F.	Install Deep Beam Rail w/Steel Tubular Backup and Type 1 Steel Posts and Anchor Bolts	\$60.00	\$12,000.00	\$125.89	\$25,178.00	\$50.00	\$10,000.00	\$100.00	\$20,000.00			\$91.96	
606	356	L.F.	Install MGS Galvanized Guardrail w/reflectors	\$19.00	\$6,764.00	\$17.50	\$6,230.00	\$25.00	\$8,900.00	\$18.00	\$6,408.00			\$20.17	
606	3	EA.	Install Type E Guardrail Assembly per ODOT Specs	\$2,000.00	\$6,000.00	\$2,080.00	\$6,240.00	\$2,500.00	\$7,500.00	\$2,100.00	\$6,300.00			\$2,226.67	
606	1	EA.	Install Type T Guardrail Assembly per ODOT Specs	\$2,000.00	\$2,000.00	\$795.00	\$795.00	\$1,000.00	\$1,000.00	\$800.00	\$800.00			\$865.00	
606	4	EA.	Install Galvanized Bridge Terminal Assembly	\$2,000.00	\$8,000.00	\$1,965.00	\$7,860.00	\$3,000.00	\$12,000.00	\$2,000.00	\$8,000.00			\$2,321.67	
606	4	EA.	Install MGS Guardrail Assembly	\$500.00	\$2,000.00	\$260.00	\$1,040.00	\$400.00	\$1,600.00	\$200.00	\$800.00			\$286.67	
INDICATES CORRECTED FIGURE(S)															
Grand Total					\$135,948.25		\$176,154.57		\$197,000.00		\$198,792.00				