

				BID TAB OF QUOTES 3-05-2025 2025 HARRISVILLE TOWNSHIP ROAD BID HARRISVILLE TOWNSHIP MEDINA COUNTY, OHIO	ENGINEER'S ESTIMATE		MELWAY PAVING COMPANY, INC. 7571 SR 83 Holmesville, OH 44633		SARVER PAVING CO. 1208 Masters Ave. Ashland, Ohio 44805		GEAUGA HIGHWAY CO. 9215 State Route 303 Windham, OH 44288-1012	
REF NO.	ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
1	253	40	Cu. Yds.	301 Pavement Repairs – 6" Full Depth (Installed in 2x3" Lifts) (T.H. 46 Seville Road)	\$270.00	\$10,800.00	\$290.00	\$11,600.00	\$300.00	\$12,000.00	\$290.00	\$11,600.00
2	254	95	Sq. Yds.	2" Bituminous Pavement Planing for Butt-Joints (T.H. 46 Seville Road)	\$10.00	\$950.00	\$10.00	\$950.00	\$10.00	\$950.00	\$25.00	\$2,375.00
3	407	120	Gals	SS-1 Tack Coat Applied @ 0.1 Gals/SY (T.H. 46 Seville Road)	\$3.00	\$360.00	\$2.50	\$300.00	\$2.75	\$330.00	\$3.50	\$420.00
4	441	70	Cu. Yds.	Asphalt Concrete Surface Course, Type 1, (449), PG 64-22, 2" Depth Avg. (T.H. 46 Seville Road)	\$230.00	\$16,100.00	\$280.00	\$19,600.00	\$240.00	\$16,800.00	\$290.00	\$20,300.00
5	422	14950	Gals	MC-3000 Seal Coat Applied @ 0.55 Gal/SY	\$3.00	\$44,850.00	\$2.75	\$41,112.50	\$3.10	\$46,345.00	\$3.60	\$53,820.00
6	422	455	Tons	Twp. Supplied (Contractor to Supply Operator & Loader) 57/67 Limestone Mix Aggregate Loaded, Spread & Rolled @ 33 Lbs/SY	\$40.00	\$18,200.00	\$35.00	\$15,925.00	\$21.25	\$9,668.75	\$33.00	\$15,015.00
7	614	1	Lump Sum	Traffic Control	\$8,360.00	\$8,360.00	\$9,500.00	\$9,500.00	\$14,185.00	\$14,185.00	\$17,000.00	\$17,000.00
8	614	2.74	Miles	Temporary Center Line, Class 1	\$1,500.00	\$4,110.00	\$900.00	\$2,466.00	\$900.00	\$2,466.00	\$1,500.00	\$4,110.00
9	617	25	Tons	24" Crushed Berm Material (2" Depth)(T.H. 46 Seville Road)	\$60.00	\$1,500.00	\$90.00	\$2,250.00	\$115.00	\$2,875.00	\$125.00	\$3,125.00
10	642	130	Feet	Stop Line, Type 1	\$6.00	\$780.00	\$3.50	\$455.00	\$3.50	\$455.00	\$5.00	\$650.00
11	642	2.74	Miles	Yellow Painted Center Line, Type 1	\$1,500.00	\$4,110.00	\$900.00	\$2,466.00	\$900.00	\$2,466.00	\$1,500.00	\$4,110.00
12	642	2	Each	Railroad Symbol Marking, Type 1	\$300.00	\$600.00	\$225.00	\$450.00	\$225.00	\$450.00	\$300.00	\$600.00
TOTAL					\$110,720.00		\$107,074.50		\$108,990.75		\$133,125.00	

AVERAGE UNIT COST
\$293.33
\$15.00
\$2.92
\$270.00
\$3.15
\$29.75
\$13,561.67
\$1,100.00
\$110.00
\$4.00
\$1,100.00
\$250.00