

				BID TAB OF QUOTES 04/02/2026 REBID 2026 HINCKLEY TOWNSHIP ROAD BID HINCKLEY TOWNSHIP MEDINA COUNTY, OHIO	ENGINEER'S ESTIMATE		MELWAY PAVING CO., INC. 7571 SR 83 Holmesville, OH 44633		KARVO COMPANIES INC 4524 Hudson Dr Stow, OH 44224-1702		AVERAGE	
REF. NO.	ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	
1	253	460	Cu. Yds.	441 Pavement Repairs – 4" Full Depth	\$250.00	\$46,250.00	\$330.00	\$151,800.00	\$320.00	\$147,200.00	\$325.00	
2	253	185	Cu. Yds.	301 Pavement Repairs – 4" Full Depth	\$300.00	\$138,000.00	\$285.00	\$52,725.00	\$280.00	\$51,800.00	\$282.50	
3	254	5080	Sq. Yds.	2.5" Bituminous Pavement Planing	\$3.00	\$15,240.00	\$2.75	\$13,970.00	\$3.30	\$16,764.00	\$3.03	
4	614	3.94	Miles	Temporary Center Line, Class 1	\$1,300.00	\$5,122.00	\$1,180.00	\$4,649.20	\$1,150.00	\$4,531.00	\$1,165.00	
5	407	1020	Gals	"Trackless" SS-1 Bit. Tack Coat @ 0.1 Gals/SY	\$3.00	\$3,060.00	\$2.40	\$2,448.00	\$2.30	\$2,346.00	\$2.35	
6	441	145	Cu. Yds.	1.00" 449 Type 1 Intermediate Course Asphalt	\$220.00	\$31,900.00	\$252.00	\$36,540.00	\$230.00	\$33,350.00	\$241.00	
7	209	0.84	Miles	Linear Grading	\$2,000.00	\$1,680.00	\$2,150.00	\$1,806.00	\$3,900.00	\$3,276.00	\$3,025.00	
8	441	215	Cu. Yds.	1.50" 449 Type 1 Surface Course Asphalt	\$220.00	\$47,300.00	\$252.00	\$54,180.00	\$250.00	\$53,750.00	\$251.00	
9	441	10	Cu. Yds.	Driveway Wedging (449 Type 1 Surface Course Asphalt)	\$280.00	\$2,800.00	\$252.00	\$2,520.00	\$245.00	\$2,450.00	\$248.50	
10	617	105	Tons	24" Wide Crushed Berm Material, 2" Depth	\$60.00	\$6,300.00	\$80.00	\$8,400.00	\$98.00	\$10,290.00	\$89.00	
11	642	4.66	Miles	Yellow Painted Center Line, Type 1	\$1,500.00	\$6,990.00	\$1,180.00	\$5,498.80	\$1,150.00	\$5,359.00	\$1,165.00	
12	642	5.04	Miles	White Painted Edge Line, Type 1	\$1,200.00	\$6,048.00	\$515.00	\$2,595.60	\$500.00	\$2,520.00	\$507.50	
13	642	65	L.F.	White Painted Stop Bar, Type 1	\$6.00	\$390.00	\$3.55	\$230.75	\$3.45	\$224.25	\$3.50	
14	422	6440	Gals	MC-3000 Seal Coat Applied @ 0.45 Gals/SY	\$3.00	\$19,320.00	\$3.00	\$19,320.00	\$5.50	\$35,420.00	\$4.25	
15	422	145	Tons	No. 8 ACBF Slag Cover Aggregate Loaded, Hauled, Spread & Rolled @ 20 Lbs/SY	\$85.00	\$12,325.00	\$120.00	\$17,400.00	\$44.00	\$6,380.00	\$82.00	
16	SS886	2150	Gals	Grip Tight or Approved Equal Fog Seal @ 0.15 Gals/SY	\$5.00	\$10,750.00	\$3.55	\$7,632.50	\$4.00	\$8,600.00	\$3.78	
17	614	1	Lump Sum	Traffic Control	\$21,525.00	\$21,525.00	\$20,000.00	\$20,000.00	\$38,000.00	\$38,000.00	\$29,000.00	
					<b>Grand Total:</b>	<b>\$375,000.00</b>		<b>\$401,715.85</b>		<b>\$422,260.25</b>		
					<b>Percent from Engineer's Estimate:</b>			<b>107.12%</b>				112.60%

				BID TAB OF QUOTES 04/01/2026 REBID 2026 LITCHFIELD TOWNSHIP ROAD BID LITCHFIELD TOWNSHIP MEDINA COUNTY, OHIO	<b>ENGINEER'S ESTIMATE</b>		<b>MELWAY PAVING CO., INC.</b> 7571 SR 83 Holmesville, OH 44633	
REF. NO.	ITEM NO.	QTY.	UNIT	ITEM DESCRIPTION	UNIT COST	TOTAL	UNIT COST	TOTAL
1	253	137	Cu. Yds.	301 Pavement Repairs – 4" Full Depth	\$300.00	\$41,100.00	\$350.00	\$47,950.00
2	422	13776	Gals	MC-3000 Seal Coat Applied @ 0.45 Gals/SY	\$3.50	\$48,216.00	\$3.00	\$41,328.00
3	422	311	Tons	No. 8 ACBF Slag Cover Aggregate Loaded, Hauled, Spread & Rolled @ 20 Lbs/SY	\$90.00	\$27,990.00	\$120.00	\$37,320.00
4	642	80	L.F.	White Painted Stop Bar, Type 1	\$6.00	\$480.00	\$3.35	\$268.00
5	614	1	Lump Sum	Traffic Control	\$13,610.00	\$13,610.00	\$10,000.00	\$10,000.00
6	614	0.18	Miles	Temporary Center Line, Class 1	\$1,300.00	\$234.00	\$1,850.00	\$333.00
7	642	0.18	Miles	Yellow Painted Center Line, Type 1	\$1,500.00	\$270.00	\$1,850.00	\$333.00
8	253	30	Cu. Yds.	301 Pavement Repairs – 6" Full Depth	\$270.00	\$8,100.00	\$350.00	\$10,500.00
					<b>Grand Total:</b>	<b>\$140,000.00</b>		<b>\$148,032.00</b>

**Percent from Engineer's Estimate: 105.74%**

<b>AVERAGE UNIT COST</b>
\$350.00
\$3.00
\$120.00
\$3.35
\$10,000.00
\$1,850.00
\$1,850.00
\$350.00